QUARRY CASE STUDY

Electronic Initiation and Waveform Analysis Improve Off-Site Blasting Effects

PROJECT SUMMARY

IMPROVING OFF-SITE EFFECTS FROM BLASTING AND INCREASING PRODUCTIVITY

Electronic initiation systems provide accurate delay timing for today's demanding blasting applications.

Electronics also provide the explosive engineer with the ability to program precise delay times to further improve blast performance including reduced peak particle velocity (PPV) and increased frequencies (Hz) which minimises ground vibration.

A central Vermont quarry converted from nonelectric detonators to Dyno Nobel's DigiShot® electronic initiation system.

This change was made to better comply with a 0.500 inches-per-second vibration limit mandated by the mineral rights holder, a global producer of industrial fillers and pigments.

PROJECT GOALS

IMPROVE VIBRATION AT SURROUNDING RESIDENTIAL STRUCTURES AND INCREASE BLAST PRODUCTIVITY

Following this stone producer's commitment to evaluate the performance of the DigiShot® electronic initiation system, Dyno Nobel recommended the use of signature hole waveform analysis (SHA).

This technology allows the user to select millisecond delay timing sequences that will reduce PPV and increase Hz for the different blast sites at the quarry and their specific seismograph monitoring locations.



Vibration monitoring device.

TECHNOLOGY APPLIED

TIMING ACCURACY AND PROGRAMMABILITY USED WITH WAVEFORM ANALYSIS SOFTWARE

The process to determine the optimum delay timing sequence for each specific blast event starts with accurate seismic data collection.

A series of seismographs are deployed at the quarry's regular monitoring locations, to capture seismic data from single test holes that are loaded and detonated on the active production benches.

Since only a single "signature" test hole is detonated, the shape of the captured waveform is based solely on the geology between the test hole and the seismograph.

The state-of-the-art waveform analysis software allows this single waveform to be used as a building block, evaluating multiple timing variables to determine the best delay sequences to program into the DigiShot electronic detonators to reduce PPV and improve Hz, which reduces structural response.



QUARRY CASE STUDY



Seismic Waveform Analysis

VALUE ADDED

LARGER BLASTS, IMPROVED GROUND VIBRATION AND INCREASED PRODUCTIVITY

Data collected from 107 separate events, comparing nonelectric blasts and DigiShot® blast events with waveform analysis, indicated that average blast size increased by 18%.

Total explosives detonated in these larger blasts increased by 34% yet produced significantly lower vibration readings. The mineral producer's mandated 0.50 inch-per-second vibration limit is now consistently achieved.

Previous blasts initiated with nonelectric detonators exceeded this limit on five separate occasions compromising their good neighbour promise. Due to reductions in ground vibration the quarry is now planning on drilling larger diameter blastholes.

Originally the quarry used a 3.5-inch diameter blasthole but due to these improvements an increase to 4-inch diameter hole will be made. This increased borehole diameter will also allow for an expanded pattern, further reducing drilling and blasting costs.

The average PPV reading recorded at all monitoring locations and at all distances for nonelectric blasts was 0.278 inches-per-second compared to the DigiShot blasts averaging 0.163 inches-per-second: a 41% decrease in the recorded PPV.

This combined with an average of a 10 Hz increase in the frequency spectra has resulted in the virtual elimination of neighbour complaints at this quarry.

This stone producer also reports improved diggability, better fragmentation and improved high wall stability.

These were a few of the unexpected benefits this producer and other quarries have experienced when new technologies are introduced and implemented as part of a better blasting program.

Dyno Nobel's Application Technology Team provides speedy turnaround when a request for waveform analysis timing is submitted by the quarry's blaster.

A specific analysis is completed for each blast event depending on the number of boreholes, rows and decks in that specific blast design.

In most cases the timing analysis is provided to the blaster on the same day as the submission, so they can prepare for the next day's blast.

This ensures the best chance to minimise off-site ground vibrations and maintain positive neighbour relations.





Dyno Nobel Asia Pacific Pty Limited (ACN 003 269 010) is a subsidiary of Incitec Pivot Limited (ACN 004 080 264). 28 Freshwater Place, Southbank VIC 3006.

® DYNO, GROUNDBREAKING PERFORMANCE, NONEL, DIGISHOT, DynoConsult and the DC device are registered trademarks of the Dyno Nobel / Incitec Pivot Limited Group.



© Dyno Nobel Asia Pacific Pty Limited 2020. Reproduction without permission is strictly prohibited.

Disclaimer: This case study is provided for informational purposes only. No representation or warranty is made or intended by Dyno Nobel or its affiliates as to the applicability of any procedures to any particular situation or circumstance or as to the completeness or accuracy of any information contained herein, and, to the full extent permitted by law, Dyno Nobel expressly disclaims any liability arising from the use of this document or the information contained herein. User assumes sole responsibility for all results and consequences.